

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-049-19283-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 13-31S-8E
2359 feet from S Section Line, 2377 feet from E Section Line
Lease Name: NEUBECKER Well #: 1
County: ELK Total Vertical Depth: 2327 feet

Operator License No.: 30917
Op Name: NEUBECKER, DWIGHT E.
Address: PO BOX 101411
FORT WORTH, TX 76185

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2327		0 SX
SURF	8.625	20		0 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/21/2016.12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: DWIGHT NEUBECKER Company: _____ Phone: (817) 942-1440

Proposed Plugging Method: Surface and production cement unknown. Plug according to KCC specifications.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 12/22/2016 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1850' gelled hole and spotted 10 sack plug. Pulled 1" and perforated casing at 1000' and 550'. Ran 1" back into 1000' and spotted 10 sack plug. Pulled up to 550' and circulated cement to surface. Pulled 1" and topped well off. A total of 203 sacks of cement were used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1900	1950		

RECEIVED
KCC DIST # 3
FEB 07 2017
CHANUTE, KS


DS
KCC WICHITA
FEB 10 2017
RECEIVED

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST SENT TO OPERATOR.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN) INVOICED

FEB 1 2017

Form CP-2/3