

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-199-20336-00-00
Spot: NWNW Sec/Twnshp/Rge: 18-12S-41W
660 feet from N Section Line, 660 feet from W Section Line
Lease Name: R.P. CATTLE CO. Well #: 1-18
County: WALLACE Total Vertical Depth: 1160 feet

Operator License No.: 33953 String Size Depth (ft) Pulled (ft) Comments
Op Name: RAVEN RESOURCES LLC PROD 4.5 1154 60 SX CMT.
Address: PO BOX 721880 SURF 7 245 60 SX CMT.
OKLAHOMA CITY, OK 73172

Well Type: GAS UIC Docket No: Date/Time to Plug: 02/03/2017 11:15 AM
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC
Proposal Rcvd. from: DAVE STEWART Company: RAVEN RESOURCES LLC DBA Phone: (405) 773-7340

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/200 # hulls.
7" surface casing set at 245' w/60 sx cement.
4 1/2" production casing set at 1154' w/60 sx cement.
TD at 1160', PBSD at 1118'.
Perforations: 930' - 966'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2017 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Top down plug. Connected to 4 1/2" casing. Loaded casing with water and established pump rate. Pressured to 1000 psi and broke to 400 psi. Pumped 60 sx cement w/200 # hulls. Maximum pressure 800 psi. Connected to 7" surface casing and pumped 25 sx cement. Maximum pressure 350 psi.

GPS: 39.01540N -101.92204W

Perfs:

Top	Bot	Thru	Comments
930	966		

KCC WICHITA
FEB 14 2017
RECEIVED

Remarks: CONSOLIDATED OILWELL SERVICE TICKET # 51,682. LEO PLACES WELL AT 4599' FSL AND 4377' FEL.

Plugged through: CSG

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CM

INVOICED

FEB 16 2017

Form CP-2/3

FEB 06 2017