

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-199-20337-00-00  
Spot: SE Sec/Twnshp/Rge: 14-12S-42W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease Name: GOODWIN Well #: 1-14  
County: WALLACE Total Vertical Depth: 1150 feet

Operator License No.: 33953  
Op Name: RAVEN RESOURCES LLC  
Address: PO BOX 721880  
OKLAHOMA CITY, OK 73172

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1144		60 SX
SURF	7	242		60 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/03/2017 9:00 AM  
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC  
Proposal Rcvd. from: DAVE STEWART Company: RAVEN RESOURCES LLC DBA Phone: (405) 773-7340

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/200 # hulls.  
7" surface casing set at 242' w/60 sx cement.  
4 1/2" production casing set at 1144' w/60 sx cement.  
TD at 1150', PBTD at 1103'.  
Perforations: 1030' - 1035', 1019' - 1022' and 966' - 1004'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/03/2017 10:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Top down plug. Connected to 4 1/2" production casing and pumped 80 sx cement w/200 # hulls. Maximum pressure 500 psi. Connected to 7" surface casing and pumped 25 sx cement. Maximum pressure 400 psi.

GPS: 39.00639N -101.94777W

Perfs:

Top	Bot	Thru	Comments
1030	1035		
1019	1022		
966	1004		

KCC WICHITA  
FEB 14 2017  
RECEIVED

Remarks: CONSOLIDATED OILWELL SERVICE TICKET # 51,680

Plugged through: CSG

District: 04

Signed Darrel Dipman  
(TECHNICIAN) CM

INVOICED

FEB 16 2017

Form CP-2/3

FEB 06 2017