

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-199-20339-00-00
Spot: SW Sec/Twnshp/Rge: 12-12S-42W
1320 feet from S Section Line, 1320 feet from W Section Line
Lease Name: AGWAY Well #: 1-12
County: WALLACE Total Vertical Depth: 1152 feet

Operator License No.: 33953
Op Name: RAVEN RESOURCES LLC
Address: PO BOX 721880
OKLAHOMA CITY, OK 73172

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1127		60 SX
SURF	7	244		60 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/03/2017 10:30 AM
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC
Proposal Rcvd. from: DAVE STEWART Company: RAVEN RESOURCES LLC DBA Phone: (405) 773-7340

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/200 # hulls.
7" surface casing set at 244' w/60 sx cement.
4 1/2" production casing set at 1127' w/60 sx cement.
TD at 1152', PBTD at 1091'.
Perforations: 1073' - 1076', 1062' - 1065' and 1016' - 1044'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/03/2017 11:30 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

"Top down plug. Connected to 4 1/2" production casing and pumped 85 sx cement w/200 # hulls. Maximum pressure 500 psi. Connected to 7" surface casing and pumped 15 sx cement. Maximum pressure 300 psi.

GPS: 39.02085N -101.93824W

Perfs:

Top	Bot	Thru	Comments
1073	1076		
1062	1065		
1016	1044		

KCC WICHITA
FEB 14 2017
RECEIVED

Remarks: CONSOLIDATED OILWELL SERVICE TICKET # 51,681

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM

INVOICED

FEB 16 2017

Form CP-2/3

FEB 06 2017