

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-199-20380-00-00
Spot: SENE Sec/Twnshp/Rge: 15-11S-42W
1980 feet from N Section Line, 660 feet from E Section Line
Lease Name: AGNEW Well #: 1-15
County: WALLACE Total Vertical Depth: 1332 feet

Operator License No.: 33953
Op Name: RAVEN RESOURCES LLC
Address: PO BOX 721880
OKLAHOMA CITY, OK 73172

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1332		70 SX
SURF	7	273		75 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/01/2017 8:00 AM
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC
Proposal Rcvd. from: DAVE STEWART Company: RAVEN RESOURCES LLC DBA Phone: (405) 773-7340

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement.
7" surface casing set at 273' w/75 sx cement.
4 1/2" production casing set at 1332' w/70 sx cement.
TD 1332', PBTB 1290'
Production casing was not perforated.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/01/2017 10:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Excell Services ran coil tubing to 1280' and tagged. Pumped 80 sx cement. Production casing full of cement. Connected to 7" surface casing and pumped 20 sx cement. Maximum pressure 300 psi.

GPS: 39.09876N -101.96269W

Perfs:

KCC WICHITA
FEB 14 2017
RECEIVED

Remarks: EXCELL SERVICES LLC COIL TUBING RIG. CONSOLIDATED OILWELL SERVICE TICKET # 51.667

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

FEB 06 2017

INVOICED Form CP-2/3
FEB 13 2017