

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-199-20371-00-00
Spot: NENE Sec/Twnshp/Rge: 10-12S-42W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: LYON Well #: 1-10
County: WALLACE Total Vertical Depth: 1302 feet

Operator License No.: 33953
Op Name: RAVEN RESOURCES LLC
Address: PO BOX 721880
OKLAHOMA CITY, OK 73172

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1285		60 SX
SURF	7	248		80 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/02/2017 1:30 PM
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC
Proposal Rcvd. from: DAVE STEWART Company: RAVEN RESOURCES LLC DBA Phone: (405) 773-7340

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement.
7" surface casing set at 248'.
4 1/2' production casing set at 1285'.
TD 1302', PBSD 1243'.
Production casing was not perforated.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2017 3:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perfs:

Excell Services ran coiled tubing to 1240'. Pumped 80 sx cement. 4 1/2' production casing full of cement. Connected to 7" surface casing and pumped 25 sx cement. Maximum pressure 300 psi.

GPS: 39.02994N -101.96358W

KCC WICHITA
FEB 14 2017
RECEIVED

Remarks: EXCELL SERVICES LLC COIL TUBING RIG. CONSOLIDATED OILWELL SERVICE TICKET # 51,698

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED

CM

FEB 16 2017

Form CP-2/3

FEB 16 2017