

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-199-20367-00-00
Spot: NENE Sec/Twnshp/Rge: 9-12S-42W
660 feet from N Section Line, 660 feet from E Section Line
Lease Name: WESTFIELD Well #: 1-9
County: WALLACE Total Vertical Depth: 1259 feet

Operator License No.: 33953
Op Name: RAVEN RESOURCES LLC
Address: PO BOX 721880
OKLAHOMA CITY, OK 73172

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1249		60 SX
SURF	8.625	247		80 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 02/02/2017 9:00 AM
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC
Proposal Rcvd. from: DAVE STEWART Company: RAVEN RESOURCES LLC DBA Phone: (405) 773-7340

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/50 # hulls.
7" surface casing set at 247' w/80 sx cement.
4 1/2" production casing set at 1249' w/60 sx cement.
TD 1259'. PBSD 1207'.
Production casing was not perforated.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2017 11:00 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Excell Services ran coiled tubing to 1200'. Pumped 90 sx cement. Communication between 4 1/2" casing and 7" casing. Shut in 7" casing. Pumped 4 1/2" casing full of cement. Connected to 7" surface casing and pumped 25 sx cement w/50 # hulls. Maximum pressure 250 psi. Filled 4 1/2' casing with 10 sx cement.

GPS: 39.02983N -101.98208W

Perfs:

KCC WICHITA
FEB 14 2017
RECEIVED

Remarks: EXCELL SERVICES LLC COIL TUBING RIG. CONSOLIDATED OILWELL SERVICE TICKET # 51,697

Plugged through: TBG

District: 04

Signed Darrel Dipman

(TECHNICIAN) INVOICED

CM

FEB 16 2017

Form CP-2/3

FEB. 8 6 2017