

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-199-20365-00-00  
Spot: NENW Sec/Twnshp/Rge: 11-12S-42W  
660 feet from N Section Line, 1980 feet from W Section Line  
Lease Name: WESTFIELD Well #: 1-11  
County: WALLACE Total Vertical Depth: 1212 feet

Operator License No.: 33953  
Op Name: RAVEN RESOURCES LLC  
Address: PO BOX 721880  
OKLAHOMA CITY, OK 73172

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1204		60 SX
SURF	7	247		75 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/01/2017 12:45 PM  
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC  
Proposal Rcvd. from: DAVE STEWART Company: RAVEN RESOURCES LLC DBA Phone: (405) 773-7340

Proposed Plugging Method: Ordered 100 sx 60/40 pozmix 4% gel cement.  
7" surface casing set at 247' w/75 sx cement.  
4 1/2" production casing set at 1204' w/60 sx cement.  
TD 1212', PBSD 1162'.  
Production casing was not perforated.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/01/2017 2:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Excell Services ran coiled tubing to 1155' and pumped 75 sx cement. Production casing full of cement. Connected to 7" surface casing and pumped 5 sx cement. Pressured to 250 psi.

GPS: 39.03000N -101.95428W

Perfs:

KCC WICHITA  
FEB 14 2017  
RECEIVED

Remarks: EXCELL SERVICES LLC COIL TUBING RIG. CONSOLIDATED OILWELL SERVICE TICKET #51,695

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

FEB 06 2017

INVOICED Form CP-2/3

FEB 16 2017