

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-199-20338-00-00  
Spot: NENE Sec/Twnshp/Rge: 23-12S-42W  
660 feet from N Section Line, 660 feet from E Section Line  
Lease Name: SWARTZ ETAL Well #: 1-23  
County: WALLACE Total Vertical Depth: 1120 feet

Operator License No.: 33953  
Op Name: RAVEN RESOURCES LLC  
Address: PO BOX 721880  
OKLAHOMA CITY, OK 73172

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1116		60 SX CMT.
SURF	7	238		60 SX

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/02/2017 11:30 AM  
Plug Co. License No.: 8273 Plug Co. Name: EXCELL SERVICES, LLC  
Proposal Rcvd. from: DAVE STEWART Company: RAVEN RESOURCES LLC DBA Phone: (405) 773-7340

Proposed Plugging Method: Ordered 150 sx 60/40 pozmix 4% gel cement w/200 # hulls.  
7" surface casing set at 238' w/60 sx cement.  
4 1/2' production casing set at 1116' w/60 sx cement.  
TD 1120'. PBSD 1080'.  
Perforations: 960' - 966', 951' - 955' and 896' - 931'

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/02/2017 1:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Top down plug. Connected to 4 1/2' casing and pumped 100 sx cement w/150 # hulls.  
Pressured to 300 psi. Connected to 7" surface casing and pumped 25 sx cement. Maximum pressure 400 psi.

GPS: 39.00091N -101.94553W

Perfs:

Top	Bot	Thru	Comments
960	966		
951	955		
896	931		

KCC WICHITA  
FEB 14 2017  
RECEIVED

Remarks: CONSOLIDATED OILWELL SERVICE TICKET # 51,699

Plugged through: CSG

District: 04

Signed Darrel Dipman

(TECHNICIAN)

CM

FEB 06 2017

INVOICED

FEB 13 2017

Form CP-2/3