

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-19262-00-00
Spot: NWNWSE Sec/Twnshp/Rge: 27-33S-11E
2431 feet from S Section Line, 2376 feet from E Section Line
Lease Name: WADSWORTH Well #: 1
County: CHAUTAUQUA Total Vertical Depth: 1250 feet

Operator License No.: 33157
Op Name: R. D. ENERGY, INC.
Address: 905 N MONTGOMERY
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	7	1300		
SURF	0	0		0 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 01/09/2017 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: ROD DICKENS Company: _____ Phone: (620) 725-3065

Proposed Plugging Method: Surface cement unknown. Run 1" to TD. Gel hole. Spot 50' plug of cement on bottom. Spot 50' plug of cement at 700'. Pull up to 350' and cement to surface.

Plugging Proposal Received By: DUANE SIMS Witness Type: PARTIAL
Date/Time Plugging Completed: 01/10/2017 12:00 AM KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

Ran 1" to 1050' gelled hole and spotted 20 sack plug. Pulled 1" and perforated casing at 700' and 350'. Ran 1" back into 700' and spotted 20 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 182 sacks of cement were used to plug this well.

KCC WICHITA
FEB 10 2017
RECEIVED


RECEIVED
KCC DIST # 3
FEB 07 2017
CHANUTE, KS

DS

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST LETTER RECEIVED BY OPERATOR.

Plugged through: TBG

District: 03

Signed: 
(TECHNICIAN)

Form CP-2/3

INVOICED
FEB 16 2017