

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-193-20847-00-00
Spot: NWSWNWSE Sec/Twnshp/Rge: 26-8S-35W
1800 feet from S Section Line, 2500 feet from E Section Line
Lease Name: FS/BRENN UNIT Well #: 1-26
County: THOMAS Total Vertical Depth: 4928 feet

Operator License No.: 3581
Op Name: RED OAK ENERGY, INC.
Address: 7701 E KELLOGG DR STE 710
WICHITA, KS 67207

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4918		125 SX
SURF	8.63	326		195 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 02/02/2017 3:15 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: PRESTON DREILING Company: RED OAK ENERGY, INC. DBA Phone: (785) 639-2099

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement w/600 # hulls.
Perforations: 4700' - 4703' Cherokee, 4715' - 4719' Johnson.
PC at 2880' w/500 sx cement.
PBSD at 4877'.

Plugging Proposal Received By: DARREL DIPMAN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 02/02/2017 3:15 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Express Well Service ran in hole with tubing to 4437'. Quality rigged to tubing and pumped 105 sx cement w/300 # hulls mixed in. Pulled tubing to 3150' and pumped 105 sx cement w/100 # hulls. Pulled tubing to 1575' and pumped 100 sx cement w/100 # hulls to circulate cement to pit area. Pulled tubing. Rigged to 4 1/2" casing and pumped 10 sx cement w/300 psi. Shut in pressure 200 psi. Rigged to 8 5/8" surface casing and pumped 10 sx cement at 200 psi. Shut in pressure 200 psi.

GPS: 39.32799 -101.19434

Perfs:

Top	Bot	Thru	Comments
4715	4719		
4700	4703		


KCC WICHITA
FEB 14 2017
RECEIVED

Remarks: QUALITY CEMENTING CO. TICKET # 7329

Plugged through: TBG

District: 04

Signed



(TECHNICIAN)

CM

INVOICED

Form CP-2/3

FEB 16 2017

FEB 03 2017