

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-19268-00-00  
Spot: SWNESW Sec/Twnshp/Rge: 23-31S-5E  
1650 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: SU-CARISING Well #: 10  
County: COWLEY Total Vertical Depth: 2346 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, LLC  
Address: PO BOX 438  
HAYSVILLE, KS 67060

String	Size	Depth (ft)	Pulled (ft)	Comments
PKR		2080		
PROD	4.5	2344		150 SX
SURF	8.625	197		140 SX
T1	2.375	2080		

Well Type: EOR UIC Docket No: E09056.3 Date/Time to Plug: 08/01/2016 8:00 AM  
Plug Co. License No.: 3004 Plug Co. Name: GRESSEL OILFIELD SERVICE, LLC  
Proposal Rcvd. from: JOE BURNETT Company: BEAR PETROLEUM LLC Phone: (316) 525-1225

Proposed  
Plugging  
Method:

AS PER KCC RULES & REGS / CIBP @ 2250 W/2 SXS PERF & CIRC. 250'-0'.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/02/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH ON WIRELINE SET CIBP @ 2250', DUMP BAILED 2 SXS CEMENT ON TOP OF CIBP. RIH ON WIRELINE PERFORATED SQUEEZE HOLES @ 250'-251' (4 HOLES). RIH W/TBG @ 260', GRESSEL ESTABLISHED CIRCULATION, MIXED & PUMPED 140 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCULATED. PLUG DOWN 5:00 PM 8-2-2016. GRESSEL CEMENT TICKET #44808. TAGGED CEMENT @ 58'. 11-23-2016, TOPPED WELL BACK TO SURFACE WITH 6 SXS CLASS A COMMON. P&A COMPLETE.

Perfs:


Top	Bot	Thru	Comments
2307	2322	CSG	

Remarks: FAILED MIT

Plugged through: TBG

District: 02

Signed

  
(TECHNICIAN)

Form CP-2/3

INVOICED  
FEB 17 2017