

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20329-00-00
Spot: SWSWSW Sec/Twnshp/Rge: 6-17S-8W
330 feet from S Section Line, 4950 feet from E Section Line
Lease Name: RATHBUN Well #: 1
County: ELLSWORTH Total Vertical Depth: 3283 feet

Operator License No.: 5399

Op Name: TREK AEC, LLC

Address: 200 W DOUGLAS, SUITE 101
WICHITA, KS 67202

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|------------|
| PROD | 5.5 | 2503 | | 200 SX |
| PROD | 5.5 | 2509 | | 75 SXS CMT |
| SURF | 8.625 | 239 | | 160 SX |

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 11/22/2016 2:00 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: TANNER NELSON

Company:

Phone: (620) 755-2571

Proposed
Plugging
Method:

As per Kansas Corporation Commission's Rules and Regulations, as per their recommendations.

Plugging Proposal Received By: JEFF KLOCK

Witness Type: PARTIAL

Date/Time Plugging Completed: 11/23/2016 10:30 AM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, pull rods and tubing out. Set CIBP at 2040' and cap with 2 sx's cement. Perforate at 1150', 800' and 290'. Run tubing to 1150' and pump 35 sx's common cement with CC and cotton hulls. Pull tubing out of hole and let set. Come back on 11-23-16 and tagged cement at 810'. Pumped 35 sx's common cement with CC at 800'. Pulled tubing to 290' and circulated cement to surface. Pulled tubing out and topped off.

| Top | Bot | Thru | Comments |
|------|------|------|----------|
| 2050 | 2058 | | |

INVOICED

FEB 17 2017

Remarks: QUALITY WIRELINE #0019 FOR SETTING CIBP. QUALITY WIRELINE #0020 FOR PERFORATING.
QUALITY OILWELL CEMENT TICKET #6583.

Plugged through: TBG

District: 02

Signed

Virgil Clothier

(TECHNICIAN)