

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-053-20809-00-00
Spot: N2S2SESE Sec/Twnshp/Rge: 36-16S-9W
480 feet from S Section Line, 660 feet from E Section Line
Lease Name: JANSSEN A Well #: 1
County: ELLSWORTH Total Vertical Depth: 3350 feet

Operator License No.: 5399

Op Name: TREK AEC, LLC

Address: 200 W DOUGLAS, SUITE 101
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2523		100 SX
SURF	8.625	257		160 SXS CMT
SURF	8.625	258		160 SX

Well Type: GAS

UIC Docket No:

Date/Time to Plug: 11/28/2016 3:00 PM

Plug Co. License No.: 31925

Plug Co. Name: QUALITY WELL SERVICE, INC.

Proposal Rcvd. from: TANNER NELSN

Company:

Phone: (620) 755-2571

Proposed
Plugging
Method:

As per Kansas Corporation Commission's rules and regulations, as per their recommendations.

Plugging Proposal Received By: VIRGIL CLOTHIER

Witness Type: PARTIAL

Date/Time Plugging Completed: 11/29/2016 1:00 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

MIRU, pull rods and tubing. Set CIBP @ 2370' and cap with 2 sx's cement. Perforate at 1150', 800', and 310'. Run tubing to 1150' on 11-28-16 and pump 35 sx's common with CC. Pull tubing out and come back on 11-29-16 to tag. Tagged cement at 825'. Pumped 35 sx's common cement with CC at 800'. Pulled tubing to 310' and circulated cement to surface. Pull tubing out and top off.

Top	Bot	Thru	Comments
2434	2442		

Remarks: QUALITY OIL WELL CEMENT #6584. THIS WELL WAS DENIED TA STATUS DUE TO HFLD.

Plugged through: TBG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

Form CP-2/3

INVOICED

FEB 17 2017