

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-21217-00-00
Spot: SESESW Sec/Twnshp/Rge: 31-24S-13E
210 feet from S Section Line, 2615 feet from W Section Line
Lease Name: DINIUS Well #: 27
County: GREENWOOD Total Vertical Depth: 1639 feet

Operator License No.: 32044
Op Name: TRIMBLE & MACLASKEY OIL LLC
Address: 110 SOUTH ST PO BOX 171
GRIDLEY, KS 66852

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		1480		
PROD	4.5	1638		60 SX
SURF	7	40		8 SX

Well Type: EOR UIC Docket No: E04497.8 Date/Time to Plug: 01/30/2017 9:00 AM
Plug Co. License No.: 32044 Plug Co. Name: TRIMBLE & MACLASKEY OIL LLC
Proposal Rcvd. from: RANDALL L. TRIMBLE Company: Phone: (620) 836-2000

Proposed Plugging Method: Perf casing @ 600' and 250'. 50' bottom cement bridge, gel spacer, 50' cement bridge @ 550', cement 250' to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: NONE
Date/Time Plugging Completed: 01/30/2017 12:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1420', pumped 15 sxs cement, pulled tubing to 570', pumped 15 sxs cement, pulled tubing to 252', pumped 75 sxs cement to surface, gel spacers between cement plugs.

Perfs:

Top	Bot	Thru	Comments
1441	1447		KCC WICHITA FEB 10 2017 RECEIVED RECEIVED KCC DIST # 3 FEB 06 2017 CHANUTE, KS MH

Remarks:

Plugged through: TBG

INVOICED
FEB 10 2017

District: 03

Signed Mike Heffern
(TECHNICIAN)

