

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-081-21235-00-01
Spot: SENESESW Sec/Twnshp/Rge: 22-27S-34W
666 feet from S Section Line, 2775 feet from E Section Line
Lease Name: PLEASANT PRAIRIE UNIT Well #: 401W
County: HASKELL Total Vertical Depth: 5350 feet

Operator License No.: 32446
Op Name: MERIT ENERGY COMPANY, LLC
Address: 13727 NOEL RD STE 1200
DALLAS, TX 75240

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5093		WITH 5 SX CMT
PC		3016		
PROD	5.5	5346	0	WITH 185 SX CMT
SURF	8.625	1635		WITH 480 SX CMT

Well Type: EOR UIC Docket No: E27880.3 Date/Time to Plug: 01/27/2017 9:30 AM
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.
Proposal Revd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5093' WITH 5 SX CMT. PLUG AT 3600' WITH 75 SX CMT. PLUG AT 1680' WITH 50 SX CMT. PLUG AT 810' WITH 50 SX CMT. PLUG AT 64' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/27/2017 12:30 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

1/26/17: CIBP @ 5093' WITH 5 SX CMT. 1ST PLUG AT 3600' WITH 75 SX CMT.
1/27/16: SHOT CASING AT 1698'. WASN'T FREE. RAN CBL. GOOD CMT TO 210'.
RAN OUT OF WATER. 2ND PLUG AT 1700' WITH 30 SX CMT. 3RD PLUG AT 810' TO
0' WITH 80 SX CMT. TOPPED OFF WITH 5 SX CMT. PUMPED 10 SX CMT DOWN
BACKSIDE. PRESSURED TO 300 PSI.

Perfs:

Top	Bot	Thru	Comments
5143	5200		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
FEB - 6 2017
KCC DODGE CITY



INVOICED Form CP-2/3
FEB 16 2017