

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-19211-00-01  
Spot: NESESE Sec/Twnshp/Rge: 6-30S-4E  
942 feet from S Section Line, 363 feet from E Section Line  
Lease Name: BRODBECK Well #: 1  
County: COWLEY Total Vertical Depth: 3465 feet

Operator License No.: 35269  
Op Name: CK OIL & GAS LLC  
Address: 906 E. TRAPP ST.  
HERINGTON, KS 67449

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3135		220 sx cement
SURF	8.625	200		165 sx cement

Well Type: SWD UIC Docket No: D10496.0 Date/Time to Plug: 11/14/2016 8:00 AM  
Plug Co. License No.: 30483 Plug Co. Name: KREMEIER, LES (DECEASED)ESTATE DBA KREMEIER PROD & OPER  
Proposal Rcvd. from: CHRIS KREMEIER Company: Phone: (785) 307-5701

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/17/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

Perfs:

SET CIBP @ 2990' W 5 SXS CEMENT ON TOP OF PLUG. CUT CASING @ 1455', LAYED DOWN CASING. RIH W/TUBING @ 317', ELITE ESTABLISHED CIRCULATION, MIXED & PUMPED 140 SXS 60/40 POZ MIX 4% GEL TO SURFACE. CEMENT CIRCULATED. CEMENT TICKET # 3038.

Top	Bot	Thru	Comments
3135	3465	OH	

Remarks: COMPLIANCE / 10 YR RULE

Plugged through: TBG

INVOICED  
FEB 16 2017

District: 02

Signed DUANE KRUEGER  
(TECHNICIAN)

JK