

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-145-20821-00-01  
Spot: S2S2NW Sec/Twnshp/Rge: 16-23S-17W  
2994 feet from S Section Line, 3917 feet from E Section Line  
Lease Name: MARTHA Well #: 16-1  
County: PAWNEE Total Vertical Depth: 4610 feet

Operator License No.: 30481  
Op Name: APOLLO ENERGIES, INC.  
Address: 10378 N 281 HWY  
PRATT, KS 67124

| String | Size  | Depth (ft) | Pulled (ft) | Comments        |
|--------|-------|------------|-------------|-----------------|
| PROD   | 4.5   | 4450       | 1818        | WITH 175 SX CMT |
| SURF   | 8.625 | 371        |             | WITH 275 SX CMT |

Well Type: EOR UIC Docket No: E24162.1 Date/Time to Plug: 02/09/2017 2:15 PM  
Plug Co. License No.: 30481 Plug Co. Name: APOLLO ENERGIES, INC.  
Proposal Revd. from: JIM BYERS Company: APOLLO ENERGIES, INC. Phone: (620) 672-9001

Proposed Plugging Method: SAND BACK TO 4180' WITH 4 SX CMT. PLUG AT 1150' WITH 15 SX GEL & 50 SX CMT. PLUG AT 400' WITH 100 SX CMT. PLUG AT 60' WITH 30 SX CMT.

Plugging Proposal Received By: LARRY HARRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 02/09/2017 4:15 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SAND BACK TO 4180' WITH 4 SX CMT ON TOP. 1ST PLUG AT 1177' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 422' WITH 100 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 4231 | 4238 |      |          |

Remarks: \*\*COMPLIANCE ISSUE: FAILED MIT\*\* USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

INVOICED

FEB 10 2017

District: 01

Signed



(TECHNICIAN)

RECEIVED  
FEB 10 2017  
KCC DODGE CITY