

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01306-00-00

Spot: NWNWNWSW

Sec/Twnshp/Rge: 13-24S-12E

2500 feet from S Section Line, 5080 feet from E Section Line

Lease Name: GEIST

Well #: 3

County: GREENWOOD

Total Vertical Depth: 1727 feet

Operator License No.: 5394

Op Name: ABDERHALDEN, R. R.

Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comment</u>
PROD	6.625	1683		75 SX
SURF	8.25	1169		75 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 12/20/2016 10:00 AM

Plug Co. License No.: 5656

Plug Co. Name: R.R.A., INC.

Proposal Rcvd. from: DWAIN STOUT

Company:

Phone: (31) 664-0972

Proposed Pump gel from TD to casing. Set a 50 ft. cement plug on bottom of casing. Pump gel to 700 ft. Set a 50 ft. cement plug.
Plugging Pump gel to 250 ft. Cement from 250 ft. to surface. Run 250 ft. of 1" tubing between surface and production casings and
Method: cement to surface.

Plugging Proposal Received By: MICHAEL HEFFERN

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 12/21/2016 2:00 PM

KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

ran tubing to 1720', pumped 10 sxs cement, pulled tubing to 800', pumped 10 sxs cement, pulled tubing to 150', pumped 170 sxs cement to surface, ran 1' pipe down back side, pumped 55 sxs cement to surface.

Perfs:

KCC WICHITA
FEB 10 2017
RECEIVED

RECEIVED
KCC DIST # 3
FEB 06 2017
CHANUTE, KS

MH

INVOICED
FEB 16 2017

Remarks:

Plugged through: TBG

District: 03

Signed

Michael Heffern

(TECHNICIAN)