

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-065-23130-00-00
Spot: SWNWSESE Sec/Twnshp/Rge: 2-8S-21W
920 feet from S Section Line, 1210 feet from E Section Line
Lease Name: GRIFFIE BENOIT Well #: 1
County: GRAHAM Total Vertical Depth: 3520 feet

Operator License No.: 7076
Op Name: BLACK DIAMOND OIL, INC.
Address: PO BOX 641
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3514		445 SX
SURF	8.625	221		150 sx

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/30/2017 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 415 sx 60/40 pozmix 4% gel cement, 500 # hulls and 10 sx gel.
5 1/2" casing cemented top to bottom.
Perforations: 3247' - 3250', 3268' - 3270', 3280' - 3286' LKC.
Bridge Plug at 3300'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/30/2017 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Quality rigged to casing, mixed and pumped 75 sx cement w/200 # hulls mixed in followed by 10 sx gel, followed by 200 sx cement w/300 # hulls. Well went on a vacuum. Rigged to 8 5/8" surface casing and pumped 5 sx cement w/100 psi. Shut in pressure 100 psi. Left 5 1/2" casing set for 1/2 hour. Pumped 35 sx cement and ran out of cement. Ordered 100 sx cement. Pumped 45 sx cement to top off 5 1/2" casing. Hole standing full.

GPS: 39.38214 -099.62559

Perfs:

Top	Bot	Thru	Comments
3484	3488		
3442	3445		
3374	3378		
3300			
3280	3286		
3268	3270		
3247	3250		
3209	3213		
3120	3124		


KCC WICHITA
FEB 14 2017
RECEIVED
INVOICED
FEB 16 2017

Remarks: QUALITY OILWELL CEMENTING TICKET # 7326

Plugged through: CSG

District: 04

Signed _____


(TECHNICIAN)

(M)

FEB 02 2017