

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-26571-00-00
Spot: SENWNW Sec/Twnshp/Rge: 11-35S-12E
4561 feet from S Section Line, 757 feet from W Section Line
Lease Name: BOWMAN SOUTH Well #: 11-1A
County: CHAUTAUQUA Total Vertical Depth: 1872 feet

Operator License No.: 35316 •

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	11	371		135 SX

Op Name: BIRCH CREEK, LLC

Address: 4009 TIMBERLINE DR
STILLWATER, OK 74074

Well Type: DH

UIC Docket No:

Date/Time to Plug: 01/11/2017 10:00 AM

Plug Co. License No.: 32884

Plug Co. Name: ELMORE'S, INC.

Proposal Rcvd. from: JOHN ROUNTREE

Company:

Phone: (918) 534-2322

Proposed Plugging Method: In accordance with KCC inspector.

Plugging Proposal Received By: DUANE SIMS

WitnessType: PARTIAL

Date/Time Plugging Completed: 01/12/2017 10:00 AM

KCC Agent: DUANE SIMS

Actual Plugging Report:

Perfs:

This well was never completed with a longstring. Surface casing is all that was set on this well. Ran 1" to 1600' gelled hole and spotted 20 sack plug. Pulled up to 900' and spotted 20 sack plug. Pulled up to 350' and pumped 40 sacks of cement. Lost circulation. Pulled 1". Came back next day (January 12, 2017) and ran 1" to 350'. Circulated cement to surface. Pulled 1" and topped well off. A total of 200 sacks of cement were used to plug this well. Well was cut off and location restored.

RECEIVED
KCC DIST # 3
FEB 07 2017
CHANUTE, KS

DS
KCC WICHITA
FEB 10 2017


RECEIVED
INVOICED
FEB 16 2017

Remarks: WELL WAS PLUGGED DUE TO INACTIVE WELL LIST.

Plugged through: TBG

District: 03

Signed



(TECHNICIAN)