

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-035-24293-00-00  
Spot: SESWNW Sec/Twnshp/Rge: 5-30S-4E  
2922 feet from S Section Line, 4615 feet from E Section Line  
Lease Name: ROCK Well #: 1-5  
County: COWLEY Total Vertical Depth: 3040 feet

Operator License No.: 35269  
Op Name: CK OIL & GAS LLC  
Address: 906 E. TRAPP ST.  
HERINGTON, KS 67449

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3010		200 SX CMT
SURF	8.625	254		165 SX CMT
T1	7.875	2915		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/14/2016 8:00 AM  
Plug Co. License No.: 30483 Plug Co. Name: KREMEIER, LES (DECEASED)ESTATE DBA KREMEIER PROD & OPER  
Proposal Revd. from: CHRIS KREMEIER Company: \_\_\_\_\_ Phone: (785) 307-5701

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DUANE KRUEGER Witness Type: PARTIAL  
Date/Time Plugging Completed: 11/17/2016 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

CIBP SET @ 2930' W 2 SXS CEMENT ON TOP OF PLUG. CUT CASING @ 1425'.  
LAYED DOWN CASING. RIH W/TUBING @ 317'. ELITE CEMENTING ESTABLISHED  
CIRCULATION. MIXED & PUMPED 135 SXS 60/40 POZ MIX 4% GEL TO SURFACE.  
CEMENT CIRCUALTED. CEMENT TICKET #3039.

Perfs:

Top	Bot	Thru	Comments
2976	2979	CSG	

INVOICED  
FEB 16 2017

Remarks: COMPLIANCE/ 10 YR RULE

Plugged through: TBG

District: 02

Signed Duane Krueger  
(TECHNICIAN)