

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-191-11553-00-00  
Spot: W2NENWSE Sec/Twnshp/Rge: 7-31S-1W  
2310 feet from S Section Line, 1786 feet from E Section Line  
Lease Name: ANSON EAST UNIT B Well #: 3-04  
County: SUMNER Total Vertical Depth: 3740 feet

Operator License No.: 3553  
Op Name: CITATION OIL & GAS CORP.  
Address: 14077 CUTTEN RD PO BOX 690688  
HOUSTON, TX 77269

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3730		60 SX
SURF	8.625	425		350 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 02/07/2017 8:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED OFS, LLC  
Proposal Rcvd. from: NEIL PFANNENSTIEL Company: CITATION OIL & GAS Phone: (785) 798-5631

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL  
Date/Time Plugging Completed: 02/07/2017 4:30 PM KCC Agent: STEVE VANGIESON

Actual Plugging Report:

Perfs:

SET CIBP @ 3680' & CAPPED WITH 2 SKS CEMENT. PERF'D 5 1/2" CASING AT 435'.  
RAN 2 3/8" TUBING TO 445 & CIRCULATED CEMENT TO SURFACE WITH 260 SX.

Remarks: BASIC COMMON CEMENT.

Plugged through: IBG

District: 02

Signed \_\_\_\_\_

(TECHNICIAN)

INVOICED  
FEB 16 2017