

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-107-24604-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 34-21S-22E
1038 feet from S Section Line, 188 feet from W Section Line
Lease Name: UNGEHEUER, D & B 342122 (6 Well #: G2-C
County: LINN Total Vertical Depth: 830 feet

Operator License No.: 5150
Op Name: COLT ENERGY INC
Address: PO BOX 388
IOLA, KS 66749

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	824		100 SX
SURF	8.625	20		8 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/15/2016 12:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: RICK RICE/COLT ENERGY Company: _____ Phone: (620) 380-1236

Proposed Plugging Method: RUN PIPE TO TD, CEMENT 100' AT TD, PULL PIPE TO 500' AND CEMENT 50', PULL PIPE TO 250' AND CEMENT TO SURFACE

Plugging Proposal Received By: LEVI SHORT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/15/2016 12:00 AM KCC Agent: LEVI SHORT

Actual Plugging Report:

RUN 2-INCH TUBING TO 819 FEET INSIDE 5-INCH PRODUCTION CASING. WITH BENTONITE SPACERS, PLACE 125 FOOT CEMENT PLUG AT 819 FEET, 50 FOOT CEMENT PLUG AT 500 FEET, THEN FILL TO SURFACE FROM 250 FEET. A TOTAL OF 60 SACKS OF PORTLAND CEMENT WERE USED TO PLUG WELL. SHUT IN PRESSURE: 100 PSI.

Perfs:

Top	Bot	Thru	Comments
727	737		

KCC WICHITA
FEB 10 2017
RECEIVED

RECEIVED
KCC DIST # 3
FEB 08 2017
CHANUTE, KS
LS

Remarks:

Plugged through: TBG

District: 03

Signed 

(TECHNICIAN) INVOICED

FEB 16 2017

Form CP-2/3