

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-191-22416-00-00
Spot: W2NWNE Sec/Twnshp/Rge: 33-34S-2E
690 feet from N Section Line, 2310 feet from E Section Line
Lease Name: NEAL Well #: 11
County: SUMNER Total Vertical Depth: 3490 feet

Operator License No.: 30425
Op Name: DNR OIL AND GAS, INC.
Address: 12741 E CALEY UNIT 142
CENTENNIAL, CO 80111

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3414		
CIBP		3426		
PROD	5.5	3490		150 SX
SURF	8.625	256		155 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/04/2016 8:00 AM
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC
Proposal Rcvd. from: CHARLES B. DAVIS/FLOYD Company: DNR OIL AND GAS, INC. Phone: (303) 825-8956

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: DAN FOX Witness Type: PARTIAL
Date/Time Plugging Completed: 08/04/2016 12:00 PM KCC Agent: DAN FOX

Actual Plugging Report:

CIBP @ 2280' CAPPED W/2 SX. RAN BACK IN AND TAGGED TOP OF CAP AT 2268'. PRESSURE TESTED CASING TO 300 PSIG FOR 30 MIN. WITH NO DROP IN PRESSURE. SHOT PERFORATIONS AT 313' RAN BACK IN WITH TUBING AND CIRCULATE 119 SX OF 60/40 POS MIX WITH 4% GEL, 2% CC AND 1/2 LB. OF POLY FLAKE, CIRCULATE TO SURFACE. CAME BACK NEXT DAY, NO DROP IN TOP PLUG, CUT OFF BELOW SURFACE.

Perfs:

Top	Bot	Thru	Comments
3428	3432		SPF
3423	3425		SPF
3416	3420		SPF
3396	3402		SPF

Remarks: PLUGGING OF THIS WELL IS A RESULT OF NOV DEADLINE.

Plugged through: TBG

District: 02

Signed _____

Daniel J. F. F.
(TECHNICIAN)

INVOICED
FEB 16 2017

✓