

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-25431-00-00
Spot: S2SWSESW Sec/Twnshp/Rge: 32-12S-17W
120 feet from S Section Line, 1650 feet from W Section Line
Lease Name: SCHMEIDLER UNIT Well #: 1
County: ELLIS Total Vertical Depth: 3666 feet

Operator License No.: 5135
Op Name: FARMER, JOHN O., INC.
Address: 370 W WICHITA AVE PO BOX 352
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3657		470 SX
SURF	8.625	222		150 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/31/2017 8:30 AM
Plug Co. License No.: 34032 Plug Co. Name: SIEMSEN WELL SERVICE INC.
Proposal Rcvd. from: VAL DREHER Company: FARMER, JOHN O., INC. DBA Phone: (785) 483-8356

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 600 # hulls and 10 sx gel.
Alt II completed.
Perforations: 3371' - 3376', 3388' - 3393', 3414' - 3417', 3434' - 3438', 3483' - 3485', 3503' - 3505', 3514' - 3516'.
PBSD @ 3643'

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/31/2017 12:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Siemsen Well Service ran in hole with tubing to 3350'. Quality rigged to tubing and pumped 10 sx gel followed by 50 sx cement w/300 # hulls mixed in. Pulled tubing to 1850' and pumped 180 sx cement w/200 # hulls mixed in to circulate cement to pit area. Pulled tubing. Topped off 5 1/2" casing with 20 sx cement. Hole standing full. Rigged to 8 5/8" surface casing and pumped 25 sx cement w/200 psi. Shut in pressure 200 psi.

GPS: 38.95842 -099.23705

Perfs:


Top	Bot	Thru	Comments
3514	3516		
3503	3505		
3483	3485		
3434	3438		
3414	3417		
3383	3393		
3371	3376		

KCC WICHITA
FEB 14 2017
RECEIVED

Remarks: QUALITY OILWELL CEMENTING TICKET # 7327

Plugged through: TBG

District: 04

Signed  (TECHNICIAN)

FEB 02 2017

INVOICED
FEB 16 2017