

State of Kansas



FORM - CP-2
Rev. 9-8-64

15-083-10105-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 30 1967

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Emerson of Cities Service Oil Co. has this date requested permission to plug the following described well:

Mr. Emerson guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 308, Great Bend, Kansas

Lease Name: Hays "A" Well No. 3

Location: C NE NW Sec. 30 Twp. 22 Rge. 23 XX (E) (W)

County Hodgeman Total Depth 4641' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Emerson was instructed to plug the well as follows:

8 5/8" to 252' circulated w/ cement. 4 1/2" to 4638' cemented

No Perforations Plug bottom w/ sand & 5 sacks cement ϕ

Top of cement 4580' Mud 4580' to 700'

Spotted 30 sacks cement 700' to 600' Mud 600' to 250'

Spotted 25 sacks cement 250' to 165' Mud 165' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

Edward J. Eves
Conservation Division Agent