



WM. H. AVERY, Governor
WILLIAM L. MITCHELL, Chairman
JOHN C. WOELK, Commissioner
HARRY G. WILES, Commissioner
RAYMOND B. HARVEY, Secretary
E. EDWARD JOHNSON, Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Powell of Braden-Deem Inc., has this date requested permission to plug the following described well:

Mr. Powell guarantees payment of the plugging fee.

Operator's full Name: Braden-Deem Inc.

Complete Address: 210-120 Bldg., Wichita, Kansas 67202

Lease Name: Henry Novotny Well No. 1

Location: SW SE NW Sec. 17 Twp. 22 Rge. 23 SE(W)

County Hodgeman Total Depth 4709' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Powell was instructed to plug the well as follows:

8 5/8" to 240' circulated w/ cement. 5 1/2" to 4709' cemented.

Top perforations 4668' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4575' Mud 4575' to 800'

Spotted 80 sacks cement 800' to 500' Mud 500' to 240'

Spotted 30 sacks cement 240' to 140' Mud 140' to 40'

Plug, Hulls & 10 sacks cement 40' to 0'.

Very truly yours,

Conservation Division Agent