



15-083-10328-0000

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Powell of Braden-Deem Inc. has this
date requested permission to plug the following described well:

Mr. Powell guarantees payment of the plugging fee.

Operator's full Name: Braden-Deem Inc.

Complete Address: 210-120 Bldg., Wichita, Kansas 67202

Lease Name: Henry Novotny Well No. 2

Location: SW SW NE Sec. 17 Twp. 22 Rge. 23 (E) (W)

County Hodgeman Total Depth 4738' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Powell was instructed to plug the well as follows:

8 5/8" to 316' circulated w/ cement. 5 1/2" to 4738' cemented.

Top perforations 4677' Plug bottom w/ sand & 5 sacks cement.

Top of cement 4620' Mud 4620' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 300'

Spot 30 sacks cement 300' to 200' Mud 200' to 40'

Plug, H_ulls & 10 sacks cement 40' to 0'.

Very truly yours,

Edmund A. Green
Conservation Division Agent