

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

DEC 20 1962
 12-20-62
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. W.H.Hill of Mack Oil Company has this

date requested permission to plug the following described well:

Mr. W.H.Hill guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company

Complete Address: 812 Union Center, Wichita, Kansas

Lease Name: Ryan Well No. # 2

Location: C SE SW Sec. 19 Twp. 22S Rge. (E) (W) 23

County Hodgeman Total Depth Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. W.H.Hill was instructed to plug the well as follows:

8 5/8" 258' Circulated w/cement. 4 1/2" 4705' Cemented.

Top Perforations, 4635'

Sand 4706' to 4500' 5 sax.cement at 4500'-4450'

Mud 4450' to 235' 10'rock bridge, 35 sax.cement 235' to 135'

Mud 135' to 50' 10'rock bridge, 15 sax.cement 50' to Surface.

Very truly yours,

[Signature]
 Conservation Division Agent