



15-083-00124-0000

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

JUL 12 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Pulley of Colorado Oil Co. has this  
date requested permission to plug the following described well:

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Colorado Oil Co.

Complete Address: Box 1030 Wichita, Kansas

Lease Name: Rehmer Well No. # 1

Location: C NW SE Sec. 8 Twp. 22 Rge. 23 (E) (W)

County Hodgeman Total Depth 4790' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

8 5/8" - 405' Circulated w/cement. 5 1/2" - 4693' Cemented. Plug back to 4638 1/2'

Top Perforations 4629'. Plug bottom w/20 Sax. cement top cement 4450'

Mud 4450' to 425' Spotted 35 Sax. cement 435' to 325'

Mud 325' to 45' Plug, Hulls, 15 Sax. cement 45' to 0

Very truly yours,

[Signature]  
Conservation Division Agent