



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
FEB 13 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Keen of Pet Inc. has this

date requested permission to plug the following described well:

Mr. Keen guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc.

Complete Address: 300 W. Douglas, Wichita, Kansas

Lease Name: Goebel "H" Well No. 1

Location: NW SW Sec. 6 Twp. 22 Rge. 23 (E) (W)

County: Hodgeman Total Depth 4700' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Keen was instructed to plug the well as follows:


8 5/8" to 404' circulated w/ cement. Mud 4700' to 900'

Spot 70 sacks cement 900' to 640' Mud 640' to 380'

Spot 25 sacks cement 380' to 300' Mud 300' to 40'

Plug, Halls & 10 sacks cement 40' to 0'..

Very truly yours,


Conservation Division Agent