

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION  
MAY 1 1973  
CONSERVATION DIVISION  
Wichita, KansasJ. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Rody of Rains & Williamson has this

date requested permission to plug the following described well:

Mr. Rody guarantees payment of the plugging fee.Operator's full Name: Rains & Williamson Oil Co.Complete Address: 220 W. Douglas, Wichita, KansasLease Name: Sebes Well No. 1Location: NE SE Sec. 32 Twp. 22 Rge. 22 (E) (W)County: Hodgeman Total Depth 4520' Oil WellGas Well  Input Well  SWD Well  D & A  Lost Hole Mr. Rody was instructed to plug the well as follows:

8 5/8" to 264' circulated w/ cement. Mud 4520' to 800'

Spot 80 sacks cement 800' to 500' Mud 500' to 250'

Spot 30 sacks cement 250' to 150' Mud 150' to 45'

Plug, Hulls &amp; 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent