

State of Kansas



15-083-20076-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 28 1969  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Musgrove of Kaiser-Francis has this

date requested permission to plug the following described well:

Mr. Musgrove guarantees payment of the plugging fee.

Operator's full Name: Kaiser-Francis Oil Co.

Complete Address: 314 Union Center, Wichita, Kansas

Lease Name: Dimmick Well No. 1

Location: C SW SE Sec. 33 Twp. 22 Rge. 22 X (W)

County Hodgeman Total Depth 4434 Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Musgrove was instructed to plug the well as follows:

8 5/8" to 283' circulated w/ cement. Mud 4434' to 850'

Spotted 80 sacks cement 850' to 550' Mud 550' to 280'

Spot 30 sacks cement 280' to 180' Mud 180' to 40'

Plug, Halls & 10 sacks cement 40' to 0'

Very truly yours,

Edgar J. Eves  
Conservation Division Agent