

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 16 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company  
Complete Address 915 Union National Bldg., Wichita, Kansas  
Lease Name MacDonnell Well No. 2  
Location SW SW NW Sec. 36 Twp. 22 Rge. (E) (W) 17  
County Pawnee Total Depth 4229'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Knight Casing Pulling Co.  
Address Box 405 Chase, Kansas License No. 436  
Operation Completed: Hour 6P Day 14 Month 1 Year 1970

The above well was plugged as follows:

Total Depth 4229' 8 5/8 csg set at 224' cwc 200 sk.  
5 1/2 csg set at 4228' cw 175 sk cmt.  
5 1/2 csg PBTB 4196' with top perf. (4145)  
Filled 5 1/2 csg W/sd (4100-4196) Dumped 5 sk cmt W/dump bailer. (4060-4100)  
Cutoff and recovered 3000' of 5 1/2 csg.  
Pumped thru 8 5/8 plug container with 20 sk gel W/500 lbs hulls, plug and 100 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Messing  
Well Plugging Supervisor

INVOICED  
DATE 1/16/70  
INV. NO. 1265-W