

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -145 -20649 -0000 (of this well)

Operator's Full Name HALLIBURTON OIL PRODUCING COMPANY
Complete Address 2915 CLASSEN BLVD. OKLAHOMA CITY, OKLA. 73106
Lease Name FRICK Well No. #2
Location NW-SW-SE Sec. 36 Twp. 22 Rge. 17 (E) (W)
County PAWNEE CO. Total Depth 4182 FE
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____

Plugging Contractor MELSO CASING PULLING
Address BOX 176 CHASE, KANS. 67524 License No. 683
Operation Completed: Hour 11:00 AM Day 12th Month MAY Year 1980

The above well was plugged as follows:
8 5/8" 321^{FE} SD. CUC. w/ 215^{SE} CMT - 4 1/2" SET AT 4138^{FE} w/ 100^{SE} CMT.
PERF'S OPEN HOLE -> BOTTOM SQUEEZED OFF WITH 35^{SE} CMT.
SHOT PIPE TWICE RECOVERED 3500^{FE}
ORDERED 140^{SE} 50/50 BORMIX 4% GEL 2% Ca-CL. - 25^{SE} GEL.
6^{SE} HULL'S -> 8 5/8" PLUG.
PUT IN 3^{SE} HULL'S - 25^{SE} GEL -> 3^{SE} HULL'S AND 140^{SE} CMT.
MAX PRESSURE 300^{PSI}

CEMENTED BY SUN CEMENTING

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5-13-80
INV. NO. 21232

RECEIVED
STATE CORPORATION COMMISSION
MAY 13 1980
CONSERVATION DIVISION
Wichita, Kansas

Signed: Martin Schmidt
Well Plugging Supervisor

5-13-80