

KANSAS

Form CP-3  
Rev. 6-4-68

f

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

SEP 25 1978

9-25-78  
CONSERVATION DIVISION  
WICHITA, KANSAS

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -145 -20,535-0000

Operator's Full Name L. D. Davis  
Complete Address Box 324, Great Bend, Kansas  
Lease Name Frick Well No. 1  
Location NW SW SW Sec. 34 Twp. 22 Rge. (E) (W) 17  
County Pawnee Total Depth 4225'  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX  
Other well as hereafter indicated         
Plugging Contractor Sterling Drlg.  
Address Sterling, Kansas License No.         
Operation Completed: Hour 3:30 A Day 23 Month 9 Year 1978

The above well was plugged as follows:

RTD=4225' 8 5/8 csg set 259' cwc 200 sk. Plg. Mat. 50-50 poz 2% total gel.  
Gunned pits, circulated heavy mud, set 50 sk cmt plug at 420' thru drill pipe.  
Heavy mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Leo Massey  
Well Plugging Supervisor

DATE 9-26-78

INV. NO. 2161-6