



KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
FEB 26 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company
Complete Address: 915 Union National Bldg., Wichita, Kansas 67202
Lease Name Boyd Well No. 1
Location SW SW SW Sec. 35 Twp. 22 Rge. 17 (E) (W) XX
County Pawnee Total Depth 4269'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated: _____
Plugging Contractor: Knight Gasing Plugging
Address: Box 405 Chase, Kansas License No. 436
Operation Completed: Hour 11P Day 25 Month 2 Year 1969

The Above well was plugged as follows:

Total Depth 4269' 8 5/8 csg set at 242' CWC
5 1/2 csg set at 4269' cw 125 sk cmt.
5 1/2 csg PBTD 4162' Perf. (4152-58)
Filled 5 1/2 csg W/sd (4100-4162) Dumped 5 sk cmt W/dump bailer. (4060-4100)
Shutoff and recov. 3390' of 5 1/2 csg.
Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk hulls, plug and 100 sk 50-50
poz cmt. W/6% total gel. Max pres. 350 lbs. SI pres. 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 2/26/69
INV. NO. 9388-W

Signed: R. D. Murray
Well Plugging Supervisor