

15-145-00348-0000

R

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 136-26

LOCATION Sw-Sw-NE

SEC. 35 TWP. 22 RGE. 17 W

Dry Hole Abandoned Oil Well ✓ Abandoned Gas Well

I have this date completed supervision of plugging of:

Well No. 1 Lease Redetzke

Operator Hilton Drilling Co. Address Box 108 St. Bend, Kans.

Field County Pawnee

Total Depth 4240 Feet.

Plugging Contractor Ace Pipe Pulling Co.

Plugging Contractor's License No. 2

Address Great Bend, Kansas.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 7/8" @ 227' c.w.c. 5 1/2" casing
set 4238' w/ 150 ss Cem. P.B. to 4139' top
perf. 4126' sanded hole to 4115' dumped 5 ss
Cem. shot off and pulled 5 1/2" casing. Pumped
20 ss fresh fill mud, Plug and 100 ss
Cem. Filling hole and surface pipe from
approx 300' to base of cellar with Cem.
Globe Cem. Co.

RECEIVED
STATE CORPORATION COMMISSION

JUL 27 1955

Warren S. Garner
District Conservation Agent

Date July 26, 1955

PLUGGING
FILE SEC 35 T 22 R 17
BOOK PAGE 136 LINE 26

CONSERVATION DIVISION
Wichita, Kansas

7-27-55