

KANSAS

## STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT STATE CORPORATION COMMISSION

RECEIVED

FEB 26 1969  
CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Colorado Oil Company

Complete Address: 915 Union Natl. Bldg., Wichita, Kansas 67202

Lease Name Boyd Well No. 7

Location SE SE SW Sec. 35 Twp. 22 Rge. 17 (E) (W) XX

County Pawnee Total Depth 4240'

Abandoned Oil Well XXX Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Knight Casing Pulling

Address: Box 405 Chase, Kansas License No. 436

Operation Completed: Hour 12:30P Day 25 Month 2 Year 1969

The Above well was plugged as follows:

Total Depth 4240' 8 5/8 csg set at 245' cwc

5 1/2 csg set at 4238' cw 175 sk cmt.

5 1/2 csg PBD 4216' with top perf. (4198-4211)

Filled 5 1/2 csg W/sd (4180-4216) Dumped 5 sk cmt. W/dump bailer. (4140-4180)

Cutoff and recovered 3365' of 5 1/2 csg.

Pumped thru 8 5/8 plug container with 20 sk gel W/5 sk gel, plug and 100 sk 50-50 poz

Cmt. W6% total gel. Max. pres. 350 lbs. SI pres 200 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2/26/69

INV. NO. 9391-U

Signed: John J. Massey  
Well Plugging Supervisor