

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

JUL - 9 1979

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

CONSERVATION DIVISION  
Wichita, Kansas  
(of this well)

API Number 15 -145-20575-0000

Operator's Full Name HALLIBURTON OIL COMPANY  
Complete Address 2915 CLASSEN BLVD. 300 CAMERON BLDG. - OKLA. CITY. OKLA.  
Lease Name REDETZKE Well No. #1 72106  
Location NW - SE - NE Sec. 35 Twp. 22 Rge. 17 (E) (W) W  
County PAWNEE Total Depth 4270 <sup>EE</sup>  
Abandoned Oil Well X Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor MELSO CASING PULLING  
Address BOX 176 CHASE, MARSHAS License No. 683  
Operation Completed: Hour 3:15 P.M. Day 6<sup>th</sup> Month JULY Year 1979

The above well was plugged as follows:

8 5/8" 324<sup>EE</sup> S.P. CWR. 225<sup>ST</sup> - 4 1/2" - 4270<sup>EE</sup> CWR. 150<sup>ST</sup>  
PERF. 4220<sup>EE</sup> to 4226<sup>EE</sup> - AT BOTTOM SAND to 4200<sup>EE</sup> AND 3<sup>ST</sup> CNT.  
SHOT PIPE AT 2700<sup>EE</sup> - RECOVERED 2700<sup>EE</sup> - PLUGGED WELL WHILE  
RECOVERING 4 1/2" CASING -  
ORDERED - 145<sup>ST</sup> COMMON CNT. - 50<sup>ST</sup> GEL - PUMPED THROUGH 4 1/2" CASING  
WITH PUMP TRUCK. - PUT - 50<sup>ST</sup> GEL AT 1000<sup>EE</sup> - 70<sup>ST</sup> CNT  
AT. 584<sup>EE</sup> - 50<sup>ST</sup> AT. 288<sup>EE</sup> AND 25<sup>ST</sup> AT 60<sup>EE</sup> AND CIRCULATED  
CEMENTED BY FLUID CEMENTING

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Melvin Schmidt  
Well Plugging Supervisor

DATE 7-10-79

INV. NO. 9986-W