

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUL 31 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Braden-Deem, Inc.

Complete Address: 210-120 Bldg., Wichita, Kansas 67202

Lease Name Henry Novotny Well No. 1

Location SW SE NW Sec. 17 Twp. 22 Rge. 23 (W)

County Hodgeman Total Depth 4709'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: None

Plugging Contractor: Braden-Deem Inc.,

Address: 210-120 Bldg., Wichita, Kansas License No. 580

Operation Completed: Hour 4:00 PM Day 29 Month 7 Year 1969

The Above well was plugged as follows:

8 5/8" to 240' circulated w/ cement. 5 1/2" to 4709' cemented.

Top perforations 4668' Plug bottom w/ sand & 5 sacks cement.

Top of cement. 4575' Mud 4575' to 800'

Spotted 80 sacks cement 800' to 500' Mud 500' to 240'

Spotted 30 sacks cement 240' to 140' Mud 140' to 40'

Plug. Hulls & 10 sacks cement 40' to 0'. Company Pump

Pulled 2900' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

Signed: Edgar J. Evers
Well Plugging Supervisor

INVOICED
DATE 7/31/69
INV. NO. 206-u