

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
AUG 4 1969
CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Administrator
500 Insurance Building
Wichita 2, KansasOperator's Full Name Braden-Deem Inc.Complete Address: 210-120 Bldg., Wichita, Kansas 67202Lease Name Henry Novotny Well No. 2Location SW SW NE Sec. 17 Twp. 22 Rge. 23 NE (W)County Hodgoman Total Depth 4738'Abandoned Oil Well Gas Well Input Well SWD Well D & A Other well as hereafter indicated: NonePlugging Contractor: Braden-Deem Inc.Address: 210-120 Bldg., Wichita, Kansas License No. 580Operation Completed: Hour 300Pm Day 31 Month 7 Year 1969

The Above well was plugged as follows:

8 5/8" to 316' circulated w/ cement. 5 1/2" to 4738' cemented.Top perforations 4677' Plug bottom w/ sand and 5 sacks cement.Top of cement 4620' Mud 4620' to 800'Spotted 80 sacks cement 800' to 500' Mud 500' to 300'Spotted 30 sacks cement 300' to 200' Mud 200' to 40'Plug, Halls & 10 sacks cement 40' to 0'. Company PumpPulled 3000' of 5 1/2" casing.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE

8/4/69

INV. NO.

232-4Signed: Edward E. Evers

Well Plugging Supervisor