

15-083-00124-0000

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 12 1965  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Colorado Oil Co.

Complete Address: Box 1030 Wichita, Kansas

Lease Name Rehmer Well No. # 1

Location C NW SE Sec. 8 Twp. 22 Rge. 23 (E) (W)

County Hodgeman Total Depth 4790'

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Forbes Casing Pulling Co.

Address: Great Bend, Kansas License No. # 49

Operation Completed: Hour 7 PM Day 9 Month 7 Year 65

The Above well was plugged as follows:

8 5/8" - 405' Circulated w/cement. 5 1/2" - 4693' Cemented. Plug back to 4638 1/2'

Top Perforations 4629'. Plug bottom w/20 Sax. cement top cement 4450'

Mud 4450' to 425' Spotted 35 Sax. cement 425' to 325'

Mud 325' to 45' Plug, Halls, 15 Sax. cement 45' to 0

Pulled 2530' 5 1/2" pipe. Company Pump.

I hereby certify that the above well was plugged as herein stated.

DATE 7-12-65

INV. NO. 1441-W

Signed: [Signature]  
Well Plugging Supervisor