


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Hodgeman County. Sec. 2 Twp. 22 Rge. 23W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW SW  
Lease Owner Chief Drilling Co., Inc.  
Lease Name Ewy Well No. #1  
Office Address Suite 905 Century Plaza, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed 9-21-69 19  
Application for plugging filed 9-21-69 19  
Application for plugging approved 9-21-69 19  
Plugging commenced 9-21-69 19  
Plugging completed 9-21-69 19  
Reason for abandonment of well or producing formation Dry hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves  
Producing formation Depth to top Bottom Total Depth of Well 4650' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	332'	8 5/8"		

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 24 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug through drill pipe @ 800' w/80 sacks cement  
Set plug through drill pipe @ 320' w/35 sacks cement  
Set plug through drill pipe @ 40' w/15 sacks cement

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Chief Drilling Co., Inc.  
Address Suite 905 Century Plaza, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Jim Robinson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jim Robinson  
Suite 905 Century Plaza, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of September, 1969

My commission expires May 9, 1971

Betty Brandt  
Betty Brandt Notary Public.

WELL LOG

Chief Drilling Co., Inc.  
905 Century Plaza  
Wichita, Kansas 67202

#1 EWY  
C SW SW Sec. 2-22-23W  
Hodgeman County, Kansas

Contractor: Chief Drilling Co., Inc.

Commenced: 9-11-69  
Completed: 9-21-69

Casing Record: Set 332' of 8 5/8" @10:30 P.M. on  
9-11-69 w/225 sacks common 1% Gel.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Surface clay and sand	0	50	2308 Gr.
Shale	50	342	2310 D.F.
Sand & shale	342	1385	2313 K.B.
Red bed & shale	1385	1517	
Anhydrite	1517	1553	
Shale & shells	1553	1946	
Shale, shells, lime strks.	1946	2093	
Shale & Lime	2093	2660	
Lime	2660	2830	
Lime & shale	2830	4095	
Lime	4095	4115	
Lime & shale	4115	4270	
Lime	4270	4650	
Total depth	4650		

<u>FORMATION TOPS</u>	
Anhydrite	1517 + 796
Heebner	3881 -1568
Toronto	3900 -1587
Lansing	3937 -1624
T.D.	4650 -2337

STATE OF KANSAS, COUNTY OF SEDGWICK) ss:

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the C SW SW of Section 2-2-23W, Hodgeman County, Kansas, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

Jim Robinson  
Jim Robinson, Office Mgr.

Subscribed and sworn to before me this 25th day of September, 1969.

Betty Brandt  
Betty Brandt, Notary Public



RECEIVED  
STATE CORPORATION COMMISSION  
SEP 26 1969  
CONSERVATION DIVISION  
Wichita, Kansas