

15.083-00066-0000


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Hodgeman County. Sec. 2 Twp. 22S Rge. 23W (X) (W)

Location as "NE/CNW/SW" or footage from lines C SW NE  
Lease Owner Franco Central Oil Company  
Lease Name Ewy-Graber Well No. 1  
Office Address 750 Fourth Nat'l Bank Bldg, Wichita, Kans.  
Character of Well (completed as Oil, Gas or Dry Hole) D & A  
Date well completed November 3, 1960  
Application for plugging filed November 3, 1960  
Application for plugging approved November 3, 1960  
Plugging commenced November 3, 1960  
Plugging completed November 3, 1960  
Reason for abandonment of well or producing formation D & A

NORTH



Locate well correctly on above  
Section Flat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Frank Broadfoot  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	186'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled with heavy mud to  
175'. Set bottom plug with  
1/2 sx hulls, and 25 sx cement.  
Set top plug @ 35' with 10 sx  
cement and 1/2 sx hulls.

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 7 1960  
CONSERVATION DIVISION  
Wichita, Kansas

11-7-60

Name of Plugging Contractor Red Tiger Drilling Company  
Address Box 173, Russell, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
(~~employed by~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) George D. Angle  
580 Fourth Nat'l Bank Bldg., Wichita, Ks.  
(address)

SUBSCRIBED AND SWORN TO before me this 4th day of November, 19 60

Mapine Head  
Notary Public.

My commission expires 11-17-62

## DRILLERS LOG

NO. 1. EWY-GRABER

CASING RECORD: COMPANY: Franco Central Oil Co. DESCRIPTION: C SW NE  
 8 5/8" @ 186' CONTRACTOR: Red Tiger Drilling Co. 2-22S-23W  
 w/115 sx cement Hodgeman County  
 Kansas  
 COMMENCED: October 21, 1960 ELEVATION: 2300 DF  
 COMPLETED: November 3, 1960 2303 RB  
 ROTARY TOTAL DEPTH: 4623'

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Post Rock Shale	0	75	
Shale Shells	75	186	
Shale & Shells	186	300	
Sand	300	420	
Shale & Shells	420	610	
Red Bed Shale	610	840	
Chalky Lime	840	880	
Red Bed	880	940	
Sand	940	1175	
Shale Shells	1175	1275	
Red Bed Shale	1275	1515	
Anhydrite	1515	1553	
Shale Shells	1553	1715	
Shale & Shells	1715	1900	
Shale & Lime	1900	2090	
Lime Shale	2090	2470	
Lime	2470	2970	
Lime Shale	2970	3130	
Lime	3130	3245	
Lime Shale	3245	3420	
Lime & Shale	3420	3585	
Lime Shale	3585	3775	
Lime & Shale	3775	3870	
Shale Lime	3870	3911	
Lime	3911	4500	
Lime & Chert	4500	4512	
Chert Lime	4512	4623	

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SIA.

NOV 7 1960  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

RED TIGER DRILLING COMPANY

*George A. Angle*  
 George A. Angle

Subscribed and sworn to before me this 4th day of November, 1960.

*Marye Head*  
 Notary Public

My Commission Expires:

11-17-62