


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 17 Twp. 22S Rge. (E) 23W(W)
Location as "NE/CNW/SW" or footage from lines SWSE SE NW
Lease Owner Braden-Deem, Inc.
Lease Name Novotny Well No. 1
Office Address
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed May 28, 19 69
Application for plugging approved May 29 19 69
Plugging commenced June 26 19 69
Plugging completed July 30 19 69
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4659 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	316	None
				5-1/2"	4659	2932'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand 4659-4600'
Rock 4600-4595'
5 sks cement @ 4695'

Shot pipe 3847' thru 2932'
Pulled 2932' 5 1/2" casing
Pumped 5 sks gel & 80 sks cement
Pumped 2 sks gel & 30 sks cement
Pumped 1 sk gel & 10 sks cement

Plugging complete

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1969
CONSERVATION DIVISION
Wichita, Kansas

8-27-69

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Braden-Deem, Inc.
Address 210 One Twenty Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Doy C. Deem (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
210 One Twenty Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of August, 19 69

My commission expires March 21, 1970

Notary Public.

ROTARY DRILLING LOG

COMPANY: TENNESSEE GAS TRANSMISSION COMPANY
1120 Liberty National Bank Building
Oklahoma City, Oklahoma

Rotary Drilling Commenced 8/3/59

LOCATION: #1 NOVOTNY
SW SE NW Sec. 17-22S-23W
Hodgeman County, Kansas

Rotary Drilling Completed 8/23/59

CONTRACTOR: PICKRELL DRILLING COMPANY
Wichita, Kansas

3 1/2' (1st log) cement'g. Report

CASING RECORD: 10 jts. of 8 5/8" 24# Republic casing set @ 216' cemented with 235 sacks cement. Cement circulated.

144 jts new 5 1/2" 14# Lone Star casing set @ 4658 1/2' cemented with 130 sacks cement.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

Clay and Shale	320'	Circ. for samples:
Red Rock and Shale	900'	
Red Bed, Shale and Shells	1470'	4095'
Shale and Shells	2185'	4227'
Shale and Lime	2605'	4237'
Lime	3120'	4357'
Lime and Shale	4010'	4625'
Lime	4022'	
Lime and Shale	4210'	
Cherty Lime and Shale	4255'	
Lime	4515'	
Lime and Shale	4625'	
Mississippi	4659'	
TD	4659'	

RECEIVED
STATE CORPORATION COMMISSION
JUN 4 1969
CONSERVATION DIVISION
Wichita, Kansas

Slope Test:

1800'	10	off
2400'	0	off
3050'	0	off
4050'	0	off

S.L.M.:

2000'	OK
3000'	OK
4000'	OK

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts
Attorney-in-Fact

STATE OF KANSAS }
COUNTY OF SEDGWICK } ss.:

On this 25th day of August, 1959, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: October 15, 1962

Julith L. Palmer
Notary Public