


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Hodgeman County, Sec. 17 Twp. 22S Rge. (E) 23 (W)
Location as "NE/CNW/SW" or footage from lines SW SW NE
Lease Owner Braden-Deem, Inc.
Lease Name Henry Novotny Well No. 2
Office Address 210 One Twenty Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Oil
Date well completed 19
Application for plugging filed May 28 19 69
Application for plugging approved May 29 19 69
Plugging commenced July 24 19 69
Plugging completed July 30 19 69
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well
Producing formation Depth to top Bottom Total Depth of Well 4738 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	405	none
				5-1/2"	4737	3000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sand 4701 - 4660'
Rock 4660-4655'
5 sks cement @ 4655'

Shot pipe @ 3704', 3608', 3512', 3418', 3322', 3227', 3131' & 3000'
Pulled 3000' - 5 1/2" casing

Pumped 5 sks gel & 80 sks cement
Pumped 2 sks gel & 30 sks cement
Pumped 1 sk gel & 10 sks cement

Plugging complete

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1969
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Braden-Deem, Inc.
Address 210 One Twenty Bldg., Wichita, Kansas 67202

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Doy C. Deem (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) _____
210 One Twenty Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 26 day of August, 19 69

Commission expires March 21, 1970
Notary Public.

ROTARY DRILLING LOG

COMPANY: Tennessee Gas Transmission Company
 665 Fourth National Bank Building
 Wichita, Kansas

LOCATION: NOVOTNY #2
 SW SW NE Sec. 17-22-23
 Hodgeman County, Kansas

CONTRACTOR: PICKRELL DRILLING COMPANY
 Wichita, Kansas

Rotary Drilling Commenced 9/30/59
 Rotary Drilling Completed 10/17/59

CASING RECORD:

Ran 406' of 8 5/8" surface casing, cemented with 300 sacks cement, 2% gel, Cement circulated.

Set 5 1/2" casing, 4752' set at 4737' K.B. cemented with 125 sacks cement, stage collar 1650', 135 bbls. Kompak. Completed at 10:00 AM 10/17/59.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

160	Clay
335	Blue shale
350	Sand rock
2400	Shale and shells
2685	Lime and shale
2960	Lime
4117	Lime and shale
4507	Lime
4560	Lime and shale
4596	Lime
4636	Lime and shale
4740	Mississippi
4740	Rotary Total Depth

Circ. for samples:

4650'
 4680'
 4694'
 4710'
 4715'
 4740'

Slope Test:

1500' 0°
 2500' 0°
 3500' 0°
 4500' 0°

S.L.M.:

2000' OK
 3000' OK
 4000' OK

RECEIVED
 STATE CORPORATION COMMISSION
 JUN 4 1969
 CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. Sebitts, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts
 Attorney-in-Fact
 C. W. Sebitts (Partner)

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 22 day of October, 1959, before me the undersigned, a Notary Public, in and for

the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: October 15, 1962

Judith L. Palmer
 Notary Public
 Judith L. Palmer