


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Hodgman County, Sec. 17 Twp. 22 Rge. 23 E/W
Location as "NE/CNW/SW¹" or footage from lines
C E/2 E/2 W/2
Lease Owner A. Scott Ritchie
Lease Name Novotny #1 Well No. _____
Office Address Wichita, Kansas
Character of Well (Completed as Oil, Gas or Dry Hole) _____



Locate well correctly on above
Section Plat

Date Well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12/29/77 _____ 19____
Plugging completed 1/6/78 _____ 19____
Reason for abandonment of well or producing formation
depleted.
If a producing well is abandoned, date of last production
_____ 19____

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Owens
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4656
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8	346	none
				4-1/2"	4645	3504'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Pumped 10 sacks cement and displaced to 4017', shot pipe at 3897', 3497', pulled 101 joints.
Halliburton pumped 10 sack s gel, 50 sacks cement at 900', mudded to 340' and ran 25 sacks
cement from 340 to 235', mud from 235 to 40', 10 sacks cement to base of cellar.

PLUGGING COMPLETE.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KELSO CASING PULLING
CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
R. DARRELL KELSO (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 16TH day of Jan., 19 78

My commission expires



Margaret Melcher
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1978

CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

Novotny #1

CASING RECORD: 8 jts. used
 8-5/8" surface casing

COMPANY: A. Scott Ritchie
 CONTRACTOR: Strata Drilling Company
 COMMENCED: December 15, 1976
 COMPLETED: December 23, 1976

DESCRIPTION: C/E/2 E/2 W/2
 Section 17-22S-23W
 Hodgeman County, Kansas
 ELEVATION: 2391' GL

TOTAL DEPTH: 4647'

<u>FORMATION</u>	<u>TO</u>	<u>FROM</u>	<u>REMARKS</u>
Surface sand and shale	0	346	Ran 8 jts. used 8-5/8" casing; set and cemented @ 330' with 200 sacks common cement, 2% gel, 3% C.C.; cement circulated. Plug down 11:00 P. M., December 15, 1976.
Shale and red bed	347	1639	
Anhydrite	1640	1672	
Shale	1673	2245	
Shale and Line	2245	4632	
Dolomite Limestone	4632	4647	

Ran two drill stem tests.

Ran electric log.

ROTARY DEPTH: 4647'

Ran 129 jts. used 5-1/2" casing; set @ 4645' with 100 sacks 60-40 pozmix, 2% gel, 8% salt. Brine pre-flush. Plug down @ 6:30 p.m., December 23, 1976.

RECEIVED
STATE COMMISSIONER OF MINES

NOV 21 1977
CONSERVATION DIVISION
Topeka, Kansas

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

Subscribed and sworn to before me this 29th day of December, 1976.

My appointment expires: November 30, 1979

Joy D. Selves
Joy D. Selves, Notary Public

