

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Hodgeman SEC. 19 TWP. 22S RGE. 23W E/W
Location as in quarters or footage from lines:

SE SW NW

Lease Owner E. K. Edmiston
 Lease Name Craghead Well No. 3
 Office Address 800 Vickers KSB&T Building, Wichita, KS 67202
 Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole
 Date Well Completed February '24, 1981
 Application for plugging filed Verbal Application
 Plugging commenced February 24, 1981
 Plugging completed February 24, 1981
 Reason for abandonment of well or producing formation _____

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas, Jr.
Producing formation _____ Depth to top _____ bottom _____ T.D. 4,692'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	327'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 4,692 ft. (rotary total depth) to 900 ft. Set plug at 900 ft. and cemented with 60 sacks cement. Filled hole with heavy rotary mud from 900 ft. to 340 ft. Set plug at 340 ft. and cemented with 35 sacks cement. Filled hole with heavy rotary mud from 340 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Sun Oil Well cementing pump truck thorough 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Oil Well Cementing, Inc.
Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, ss.

Dean Britting, Agent ~~(employee of owner)~~ ~~xxx (owner)~~ ~~xxx operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting
251 N. Water Suite 10, Wichita, KS
(Address) _____ 67202

SUBSCRIBED AND SWORN TO before me this 6th day of March, 19 81

Elsie Willison RECEIVED
Elsie Willison - Notary Public STATE CORPORATION COMMISSION

My Commission expires: July 25, 1982

MAR 19 1981

CONSERVATION DIVISION
Wichita, Kansas

3-19-81

